

Case Study



PROJECT NAME / LOCATION

Ashleworth Manor, Ashleworth, Gloucester

NO 1000

JOB SPECIFICS

Approx. Value

£150,000

Type of Works

Flood Repair Works

Property Type

Detached Cottage

Client / Customer

Elrick Smith Limited

Scope Of Works

One of the many damaged properties in Gloucester damaged during the Summer 2007 UK floods. Flood water in this particular property rose to approx. 600mm.

Works included:

Remove and replace plaster to 800mm height and reinstate to match existing undamaged plaster. Re-paper with Hessian paper and foil-backed lining paper. Remove all stains to stone fireplace using specialist cleaning solution. Clean off all mud stains to doors and apply 3 flood coats varnish. Sand and Re-polish Woodblock Floor. Apply 3 coats of Cuprinol wood preservative to affected woodwork and allow to make good French Polished finish



Antares Construction Ltd

5 Campbell Street, Brockmoor, Brierley Hill, West Midlands DY5 3YG - Tel: 01384 263953 / Fax: 01384 573435

Registered In England No. 4693030 - Registered Address: Swinford House, Albion Street, Brierley Hill DY5 3EL

www.antares-ltd.co.uk

Completed Repair Works

Staircase Repairs



Lime Plaster Repairs





Door Repairs



Fireplace Repairs



Floor Repairs



Repairs to Mudstone Plinths / Stonework



Full Details of Previous Projects are available on our website - www.antares-ltd.co.uk